

ITEM	DESCRIPTION	UNIT	QTY		AMOUNT (GH¢)
<b>RENOVATION OF MUNICIPAL LABOUR OFFICE BONO- SUNYANI</b>					
	<b><u>Fence wall</u></b>				
	<b><u>D. GROUND WORKS</u></b>				
	<u>D20: EXCAVATION AND FILLING</u>				
	<u>Excavating:</u>				
A	Pits(40Nr) maximum depth not exceeding 2.00m	m <sup>3</sup>	9		
B	Trenches; width exceeding 300mm maximum depth not exceeding 2.00m	m <sup>3</sup>	32		
	<u>Disposal; surplus excavated materials:</u>				
C	Off site	m <sup>3</sup>	10		
	<u>Filling:</u>				
D	Filling to excavations average thickness ≤ 250mm; depositing in layers and well compacted	m <sup>3</sup>	5		
	To Collection				

ITEM	DESCRIPTION	UNIT	QTY		AMOUNT (GH¢)
	<b><u>E. IN-SITU CONCRETE/LARGE PRECAST CONCRETE</u></b>				
	<b><u>E.10: MIXING/CASTING/CURING/IN-SITU CONCRETE</u></b>				
	<i><u>Reinforced in-situ concrete Grade C25/20 in:</u></i>				
A	Foundations, (Column base - 13Nr)	m <sup>3</sup>	9		
B	Foundation, strip, and aprons, thickness 225mm	m <sup>3</sup>	8		
C	Columns (40Nr)	m <sup>3</sup>	11		
	<b><u>E.20: FORMWORK FOR IN-SITU CONCRETE</u></b>				
	<i><u>Formwork and basic finish.</u></i>				
D	Columns (40Nr)	m <sup>2</sup>	360		
	<b><u>E.30: REINFORCEMENT FOR IN-SITU CONCRETE</u></b>				
	<i><u>Reinforcement; mild steel bars to B.S. 4449</u></i>				
E	In column 8mm	kg	170		
F	In column 12mm	kg	426		
	To Collection				

ITEM	DESCRIPTION	UNIT	QTY		AMOUNT (GH¢)
	<b><u>F. MASONRY</u></b>				
	<b><u>F10: BRICK/BLOCK WALLING</u></b>				
	<i>Solid sandcrete blocks, 450mm x 225mm; in cement and sand (1:4) mortar joint not exceeding 12mm thick</i>				
A	150mm thick in footing walls	m <sup>2</sup>	108		
B	125mm	m <sup>2</sup>	259		
	<b><u>M.20: PLASTERED/RENDERED/ ROUGHCAST COATINGS</u></b>				
	<i>Mortar: cement and sand (1:4) steel trowelled as render, 13mm to:</i>				
C	Walls, width exceeding 300mm	m <sup>2</sup>	720		
	<b><u>J. WATERPROOFING</u></b>				
	<b><u>J40: FLEXIBLE SHEET TANKING/DAMP PROOF MEMBRANE</u></b>				
D	Damp proofing membrane, 0.5mm thick plastic sheets	m <sup>2</sup>	74		
	<b><u>M. SURFACE FINISHES</u></b>				
	<b><u>M10: SAND CEMENT/CONCRETE/GRANOLITHIC/ SCREEDS/FLOORING</u></b>				
	To Collection				
	<b><u>COLLECTION</u></b>				
	Page No. bill 1-1				
	Page No. bill 1-2				
	Page No. bill 1-3				
	<b><u>Fence wall</u></b>				
	Sub total				
	Carried to form of tender				

# **RENOVATION OF MUNICIPAL LABOUR OFFICE BONO- SUNYANI**

ITEM	DESCRIPTION	UNIT	QTY		AMOUNT (GH¢)
	<b><u>M. 60: PAINTING/CLEAR FINISHINGS</u></b>				
	<i><u>Two undercoats and one finishing coat of Emulsion Paint</u></i>				
A	Cement rendered walls girth; exceeding 300mm ( Fence wall)	m <sup>2</sup>	518		
B	Cement rendered walls girth; exceeding 300mm ( Office)	m <sup>2</sup>	325		
	<i><u>One coat primer to general wood surfaces prior to fixing.</u></i>				
	<i><u>Two finishing coat of Gloss Oil Paint to general wood surfaces</u></i>				
C	girth; not exceeding 300mm	m	22		
D	girth; exceeding 300mm				
	Sub-total				
	Painting to form of tender				